| Description of work. | Per | Quantity. |
|---|---|---|
| Ridging with new ornamental tiles .. ... ... | R. ft. | 100 |
| Removing and re-fixing the ornamental ridge tiles with ⅓ new tiles, set in cement | „ | 44 |
| Ridging with new ordinary Mangalore tiles set in cement ... | „ | 76 |
| Removing and re-fixing the old ordinary ridge tiles in cement ... | „ | 76 |
| Iron tie bars with necessary iron shoes work, etc., complete ... | Each | 5 |
| Ordinary zinc sheets to valleys .. ... ... | Sqr. | 2·68 |
| Constructing V-shaped drain with brick in cement .. .. | R. ft. | 67 |
| Teakwood doors pannelled with locks and keys, complete .. | Sq. ft. | 308 |
| Teakwood windows with glazed shutters inside and pannelled shutters outside, with iron bars, etc., complete | „ | 246 |
| Teakwood ventilators with glazed shutters .. ... | „ | 84 |
| Teakwood eave boards, ornamental ... .. | R. ft. | 250 |
| Teakwood screen with necessary moveable doors including iron work, etc., complete with 1½" thick plank | Sq. ft. | 126 |
| Teakwood screen semi-circular portion including iron works, etc., complete with 1"-thick planks | „ | 77 |
| Wood oiling to wood work, 2 coats .. .. ... | Sqr. | 118·72 |
| Chocolate painting, 2 coats .. ... .. | „ | 17·61 |
| Cornice work .. ... .. | R. ft. | 420 |
| Flagging with Cuddapah slabs including asphalte-pointing and 6" sand bedding | Sqr. | 9·75 |
| Flooring with Mangalore square tiles and cement pointing (fixed on concrete bedding) | „ | 22·15 |
| Lime mortar pointing ... ... ... ... | „ | 5·36 |
| Fixing Mangalore finials ... ... .. | Each | 4 |
| Wire fencing— | | |
| Clearing site and levelling the grounds . .. | Lump sum. | |
| Earthwork, excavation and forming ... ... ... | Cyd. | 5 |
| Burnt stone in lime mortar ... .. .. | C. ft. | 45 |
| Burnt brick in lime mortar ... ... .. | „ | 162 |
| Lime mortar plastering .. ... ... | Sqr. | 1·17 |
| Cornice work and ornamental capital to the gate ... ... | Lump sum | |
| 932 R. ft. wire fence 4' high with 5 lines of wires, 80 angle iron standards and necessary fastenings (as per Richardson & Cruddas' Catalogue, page 253) | R. ft.<br>Mile | 932 |
| Cast-iron angle posts with wrought-iron stays and stay plates ... | Each. | 2 |
| Wrought-iron straining posts with stays and stay plates ... | „ | 4 |
| Packing charges, Railway freight from Bombay to Chikmagalur work site | Lump sum. | |
| Preparing and fixing a teakwood gate with iron works complete and with painting | Sq. ft. | 48 |
| Erecting fencing .. ... ... ... | R. ft. | 932 |

H. J. MOLLOY, *Executive Engineer.*

## MARIKANIVE DIVISION.

*Dated 22nd July* 1905.

It is hereby notified that a sum of Rs. 12-14-9 is outstanding in the books of this office as arrears due to one contractor Srinivasachar, son of Ramaswamiengar, retired Record clerk, Dodpetta, Mysore, who has not claimed the amount in spite of repeated reminders from this office and that, if the said sum be not claimed within three months from this date, the amount will be credited to Government.

H. D. RICE, *Offg. Executive Engineer.*

## BANGALORE CITY MUNICIPALITY.

*Notification dated —— July* 1905.

It is hereby notified for the information of the public that a sum of Rs. 32-6-0, being the amount due to one contractor Subbanna of Mavalli near Lal-Bagh, on account of laterite collected by him for repairing roads in the 1st Division, is lying unclaimed in the office of the undersigned. If the amount is not claimed within six months from this date, the money will be forfeited to Municipality.

*Notice dated 31st, July* 1905.

The public are hereby informed that the avenue road will be closed for traffic for about three weeks from the 3rd proximo on account of extending the tunnel of the main drain near the vegetable market.

A. S. NAGAVKAR, *President.*